



# Washington Park Boardwalk

## Project Description

- Construction of 475 feet of boardwalk and fishing piers, made from recycled composite plastic material, at the lagoon in Washington Park, located in Springfield, Illinois.



Owner – Springfield Park District  
 Architects – Bruner, Cooper & Zuck, Inc.  
 Completion Date – May 2004  
 Contract Value – \$180,000



## Project Details

- Placement of ninety 12" diameter concrete-filled drilled shafts to the lagoon bottom.
- Placement of over 5,000 square feet of structural composite fiber lumber materials.
- Installation of integral benches and fishing docks.
- Placement of over 6,000 square feet of shoreline stabilization riprap.

## Unique Challenges

- Working within a highly-trafficked urban park setting.
- Using new composite materials.
- Unstable soil conditions at the bottom of the lagoon supporting the drilled piers.
- Keeping the public out of the work zone.
- Layout of the drilled shaft locations in water.

## Contact Information

Halverson Construction Co., Inc.  
 620 North 19<sup>th</sup> Street  
 Springfield, Illinois 62702  
 Phone: 217-753-0027 | Fax: 217-753-1904